

SRF in Storage Rings

Michael Pekeler

ACCEL Instruments GmbH
51429 Bergisch Gladbach
Germany



SRF in Storage Rings

Michael Pekeler

ACCEL Instruments GmbH
51429 Bergisch Gladbach
Germany



TESLA type cavity: racing horse, >25 MV/m



This talk cavity: working horse, ~ 8 MV/m
but ~ 250 kW cw power to the beam





ACCEL

Advantages of SRF versus NC for storage rings

- Operation at high voltage possible (typical value: 2 MV per cavity)
- Operation at high power possible (up to about 250 kW per cavity)
- HOM free design possible, all HOMs can propagate through the beam tubes to HOM dampers, ferrite beam pipe HOM loads or loop HOM couplers

This are the three main reasons, why new high current storage rings are more and more considering SRF for their RF system

First installations:

TRISTAN, HERA, LEP

B-Factories:

KEK-B, CESR

New Installations:

**IHEP, NSRRC, CLS, DLS, SSRF,
SOLEIL, LHC**

higher harmonic cavities:

SLS, ELLETRA, BESSY





ACCEL

TRISTAN at KEK

- 32 superconducting 5-cell cavities (509 MHz)
- 16 cavities installed in 1988, 16 cavities installed in 1999
- 200 MV provided to the beam, operation until 1995



Two cavities inside one vacuum vessel



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005

- 288 superconducting 4-cell cavities (352 MHz)
- Installation completed 1999
- More than 3600 MV provided to the beam, operation until 2002


Development of
Nb/Cu deposition
technology and
transfer of technology
to European industry



Four cavities inside one vacuum vessel



- 16 superconducting 4-cell cavities (500 MHz)
- Installation in 1991
- 30 MV provided to the beam, operation will stop probably in 2007



Two cavities inside one vacuum vessel







KEK B-factory High Energy Ring (HER)

ACCEL

Resonant frequency	508.887 MHz
R/Q	93 Ohm
Q_0	10^9
Q_{ext}	7×10^4
Operating temperature	4.5 K
Accelerating voltage	1.5 MV



KEKB HER:
8 GeV e^- storage ring



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005

	Design	achieved
Number of SC cavities	8	4 at the commissioning 8 since Sept. 2000
Beam intensity	1.1A in 5000 bunches	1.34 A in 1389 bunches
Bunch length	4 mm	6 - 7 mm
Max RF voltage w/o beam	-	> 2.5 MV/cavity (2 – 2.8 MV/cavity)
RF voltage with beam	1.5 MV/cavity	1.2 – 2 MV/cavity
Q-value	1 x 10 ⁹ at 2 MV	0.5 – 2 x 10 ⁹ at 2 MV
RF power transferred to the beam	> 250 kW/cavity	300 - 350 kW/cavity 400 kW/cavity in max.
HOM power	5 kW at 1.1 A	14 - 16 kW at 1.34 A

RF Power at 1.27 A:

RF power of 2.4 MW was transferred to the beam by 8 SC cavities.






ACCEL

KEK B Luminosity records

- 1998 Commissioning with 4 SC
- 1999 **380** kW to the beam.
Physics run start.
- 2000 Installation of next 4 SC
- 2001 $L_{\text{peak}} = 6.9 \times 10^{33} \text{ cm}^{-2}\text{s}^{-1}$
HOM of each SC: **5 kW**.
- 2002 $L_{\text{peak}} = 8.2 \times 10^{33} \text{ cm}^{-2}\text{s}^{-1}$.
Beam of HER reached **1 A**.
- 2003 $L_{\text{peak}} = 1.06 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Beam of HER reached **1.1 A**
HOM of each SC: **10 kW**.
 $L_{\text{peak}} = 1.13 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Beams of HER reached **1.18A**
- 2004 **Continuous Injection mode**
1.25A, **16kW** of HOM.
- 2005 $L_{\text{peak}} = 1.58 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
with **1.27A**(HER)
.... still growing up



Future plans: Super KEK B

- Required RF power: 460 kW/cavity.
- Traveling wave of 500 kW demonstrated at a module test stand in 2003
- Spare module built and installation planned



Michael Pekeler, ACCEL
SRF in storage rings


12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005




ACCEL

KEK B HOM dampers


- Absorbed power up to 18 kW for SBP damper and 25 kW for LBP damper (good for 2 A operation)
- The surface temperature reached near 200 C.
- Out gas rate to be measured next



Small Beam Pipe HOM Damper



Large Beam Pipe HOM damper






Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



ACCEL

Super KEK B dreams



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005




ACCEL

KEK B technology cooperation with MELCO

KEK together with MELCO currently produces two SRF modules for the BEP II two ring e⁺e⁻ collider for τ -charm physics at IHEP, Beijing, China

- Two modes of operation: collider and SR facility
- Required voltage: 1.5-2 MV per cavity

Redesign of cavity from 509 MHz to 500 MHz was necessary




500 MHz module



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



KEK spare module (blue)
IHEP module (white)

- **Contract (Sep/2003)**
- **Vertical cold test (Dec/2004)**
- **Delivering of cavity modules (April/2005)**
- **Vacuum design and fabrication (IHEP, Sep/2005)**
- **Final assembling (Oct/2005)**
- **Horizontal power test (Dec/2005)**
- **Installation (Jan/2006), Commissioning (Jun/2006)**





ACCEL

LHC modules: Nb/Cu technology

- Design field is 2MV per cavity, installation planned for April 2006
- 16 MV required per beam => 2 modules per beam needed
- 4 modules or 16 cavities needed for operation of LHC
- 21 cavities ordered from industry => one spare module + one spare cavity



Four single cell cavities (400 MHz) in one vacuum vessel



Michael Pekeler, ACCEL
SRF in storage rings


12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



ACCEL

LHC modules: assembly status and horizontal test

- Two modules assembled and high power test finished
- Each cavity: > 3 MV reached
- Two more modules at assembly



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005




ACCEL

LHC modules: spare cavity

Spare cavity can be tested in Horizontal test cryostat as well

Tuner system

HOM



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005




ACCEL

SOLEIL: Nb/Cu technology

SOLEIL: 2.75 GeV, 500 mA light source

- Nb/Cu single-cell HOM damped cavities
- Designed and built by Saclay/CERN collaboration
- 352 MHz
- 1.5 MV/cavity
- LEP input couplers @ 200 kW
- loop HOM couplers



What the beam sees from the SOLEIL module

Two single cell cavities (352 MHz) in one vacuum vessel



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



SOLEIL: test results and refurbishment

ACCEL

High power test at CERN 1999

- 2.5 MV reached in each cavity
- 120 kW SW operation of the couplers

Beam test in ESRF in 2001

- 3 MV provided to the beam
- 190 kW transferred to the beam through each coupler

Weak points observed:

- too much HOM power (2 kW) from fundamental mode
- too high thermal losses

Decision 2002:



- improve HOM coupler design
- introduce thermal shield

Refurbishment: new rinsing of cavities


- new vertical test in 2003

New high power test at CERN in 2005

- 2.5 MV reached in each cell (spec is 1.5 MV)
- 200 kW full reflection through each coupler (spec is 150 kW TW)
- rejection of fundamental mode ok (now -34 dB, 1999: -19 dB)
- thermal losses reduced to 51 W (1999: 117 W)



SOLEIL: future plans



Thermal shield



Refurbished cryomodule prior horizontal test

SOLEIL decided to order one more module from industry,
offers are received already
decision on supplier within one or two months from now







ACCEL

Cornell: CESR III modules

4 superconducting B-cell cavity cryomodules

Resonant frequency	499.765 MHz
R/Q	89 Ohm
Q_0	10^9
Q_{ext}	2×10^5
Operating temperature	4.5 K
Accelerating voltage	up to 3 MV
Static heat leak	30 W



Highlights:

- **1994:** Beam test, demonstration of high current operation
- **1997:** First SRF cavity installed and routine operation
- **1999:** First storage ring to run entirely on SRF cavities



Michael Pekeler, ACCEL
SRF in storage rings




12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



ACCEL

Cornell: CESR III performance

Peak luminosity	$1.3 \times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$
Beam current	0.78 A
RF voltage with beam	1.85 MV/cavity (1.6 - 2)
Q_0	1×10^9 at 2 MV $0.3 - 1 \times 10^9$ at 2.7 MV
Max. power transferred to beam	300 kW/cavity (360 kW forward power)
HOM power	5.7 kW/cavity at 0.75 A



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



Cornell: CESR c and CESR chess

CESR-CHESS light source ($E=5.3$ GeV, $I_{\text{beam}}=500$ mA)

- similar though somewhat relaxed requirements as for CESR-III due to lower beam current
- emphasis on long beam lifetime, short bunches are not required hence high RF voltage is not needed (1.65 MV/cavity)

CESR-c tau/charm factory ($E=1.55\text{--}2.5$ GeV)

- ❑ high luminosity
strong IR focusing and short bunch length (1 cm)
high RF voltage ($1.85\text{--}3$ MV/cavity)
 - ❑ high luminosity
high RF voltage
 - ❑ low energy
low beam energy loss per turn & lower beam current
low RF power ($40\text{--}160$ kW)
- passive cavities**


Successful operation since 2003





ACCEL

Cornell: technology transfer to ACCEL



Technology transfer



2 modules

Taiwan Light Source

2 modules




Turn-Key Systems

2 modules



Canadian Light Source Inc.

3 modules



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



ACCEL

Turn key Cornell style SRF modules

Guaranteed module performance: $V > 2 \text{ MV}$, $Q > 5 \times 10^8$

Scope can cover

- Cavity production
- Surface preparation
- Vertical test
- Coupler production
- Coupler conditioning
- HOM loads
- Module assembly
- Installation
- Commissioning
- Valve boxes
- transfer lines
- SRF Electronics
- LLRF




Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005




ACCEL

Cavity preparation for vertical test



Closed loop BCP




HPR



Assembly in clean room



Packing and shipping for vertical test



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005




ACCEL

Bulk Nb Cavity preparation and test results

Preparation is done at ACCEL as follows:

- Degreasing
- Buffered chemical polishing (1:1:2), in closed loop chemistry, acid actively cooled to temperatures below 15 °C
- Water Rinsing > 17 MΩcm
- High pressure water rinsing (100 bar)
- Drying by pumping

- All test results achieved in consecutive preparations / tests
- All field values limited by available RF power



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



Special transport frame for shock absorption



Transport in air ride truck



Overseas transport



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



ACCEL

Installation into the NSRRC storage ring

國家同步輻射研究中心 簡訊
NSRRC Newsletter

用戶專訪：王瑜教授
專文：第十屆用戶年會暨研討會
特稿：在NSRRC的十一年快樂歲月

No. **57**
2005年1月
www.nsrrc.org.tw



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005

Two modules for Cornell, two modules for Taiwan Light Source and two modules for Canadian Light Source



Cornell

- delivered in winter 2002 and summer 2003
- both modules are operating in CESR at up to **2.4 MV/m and up to 160 kW**

Canadian Light Source

- delivered in summer 2003 and summer 2004
- first Light Source that was commissioned with superconducting RF
- both modules operated in the machine, first one operated for more than one year, then removed in order to install second one. First one now serves as hot spare.
- first one operated at up to **2.5 MV and above 200 kW**, second one up to **2.4 MV and 160 kW**, maximum beam current so far **205 mA**.

Taiwan Light Source at NSSRC

- delivered in spring 2004 and winter 2004
- one module operating in the machine since fall 2004 at **1.6 MV and up to 85 kW**
- **400 mA stored in the ring**, upgrade goal achieved
- second module commissioned on test stand at NSRRC to **1.6 MV**: hot spare

All modules achieved guaranteed performance






ACCEL

Three modules for Diamond Light Source

- all three cavities tested
- four windows conditioned
- first module will be delivered this month
- installation starts in August
- second module under assembly
- third module: assembly starts in September



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005



ACCEL

Super 3HC modules for SLS and ELETTRA

Scaled version (1.5 GHz) of SOLEIL module, HOM damping by loop couplers, developed from collaboration of CEA, PSI, Sinchrotron Trieste and CERN,

1 MV @ $Q > 1 \times 10^8$, operated at 4.5 K

- factor of 3 on bunch lengthening achieved
- factor of 2 on beam life time achieved


Cold mass assembly at CEA



In class 100 clean room



SLS cryomodule



ELETTRA cryomodule





Michael Pekeler, ACCEL
SRF in storage rings


12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005

Landau module for BESSY

- Scaled CESR type cavity (1.5 GHz)
- ferrite type beam tube HOM dampers
- 0.5 MV at $Q=8 \times 10^7$ achieved at 4.5 K
- up to now only off line test



Family trees of superconducting RF systems





ACCEL

Summary / New projects


Three different reliable and proven superconducting RF design for high current storage ring RF systems can be purchased from industry,
Voltage around 2 MV per cavity, power transferred to the beam around 250 kW

SSRF (Shanghai Light Source) will decide this month on industrial supplier for their storage ring RF system, future potential projects: NSLS II, PETRA III, TPS, ILC-DR

Three SRF Modules for Storage Ring of Shanghai Synchrotron Radiation Facility (SSRF)

Requirements to RF System	Phase I (4IDs)	Phase II (IDs full)
RF Frequency	499.654 MHz	499.654 MHz
Beam current	200 ~300 mA	300 mA
Total loss per turn	~1.64MeV/500 kW	~2.08MeV/620 kW
V_{acc}	≥ 4 MV	≥ 4 MV
RF stability	$\leq \pm 1\%$	$\leq \pm 1\%$
RF phase stability	$\leq \pm 1^\circ$	$\leq \pm 1^\circ$

Basic parameters of each set SRF module	
RF Frequency/Tuning range	499.654 MHz/ ± 200 KHz
Eacc in vertical test	>12 MV/m
Q_0 (@Eacc=8MV/m)	1×10^9
Accelerating voltage	2 MV
Dynamic loss/Total cryogenic loss	70W/100W
Q_{ext}	$1.8 \pm 0.2 \times 10^5$
Power transferable to the beam	250 KW



Michael Pekeler, ACCEL
SRF in storage rings

12th International Workshop on RF Superconductivity
Ithaca, New York, USA, July 10-15, 2005

I would like to thank:

Wolfgang Anders (BESSY)
Sergey Belomestnykh (Cornell)
Pierre Bosland (CEA)
Takaaki Furuya (KEK)
Morten Jensen (DLS)
Liu Jianfei (SSRF)
Mark de Jong (CLS)
Pierre Maesen (CERN)
Catherine Thomas-Madec (SOLEIL)
Chaoen Wang (NSRRC)
for helping me preparing the talk

Many thanks to the staff of Cornell, Canadian Light Source and NSRRC for their help, support and hospitality during module commissioning and installation

