

# Planning for the New Linear Collider Test Facility at FNAL & progress on 3.9 GHz SRF (or Do we have a plan?)

H Edwards

SRF 2005

July 13, 2005

# Political statements

- "The U.S. Department of Energy has expressed its interest in the possibility of hosting a linear collider, at Fermilab, subject to the machine being affordable and scientifically validated by physics discoveries at the LHC." From DOE for inclusion in Holmes EPP2010 talk.
- "The ILC Americas regional plan is for FNAL to assume the role of lead laboratory for ILC SRF technologies, working in close partnership with other US SRF centers, including TJNAF, Argonne and Cornell." JLab-Fermilab MOU
- US ILC Linac responsibilities-FNAL and SLAC
  - FNAL- Main Linac superconducting part & RF control
  - SLAC- main Linac RF power

# Outline of this talk

- Development of Infrastructure
  - Buildings
  - Cryo
- Planned Development Stages & Collaborators
  - Schedule highlights
  - Involvement of collaborators
- Technical Infrastructure & Components
  - Chemistry at ANL
  - Horizontal Test Dewar (HTD)
  - Cryo Module Assembly Facility (CAF)
  - Capture Cavity #2
  - PhotoInjector
  - 3.9GHz SRF Development Results
  - Materials Development Effort

# Long term R&D goals for ILC work

- Develop and test Main Linac components and subsystems
- Strengthen US & US Industry SRF capability
- Develop Fermilab expertise and capabilities
- Collaborate with other US Labs to make best use of existing capabilities
- Collaborate with International Partners
- Specific goal-
  - Module string with Beam- 4 modules & Photoinjector
  - Capability for iterative process & test of cavities & modules
- Infrastructure development planning
  - Long lead time items require looking for suitable locations for the module assembly & test

# Geography

NewMuon- ILC Modules & Injector

MP9- CAF Cryo Mod Assembly

Meson Hall- PD dev

Cryo Test Facility CTF  
~60W @2K

(Central Helium Liquifier)





CTF cryo test  
Facility (60W@2K)

Meson Hall  
PD dev plus

MP9- CAF  
cavity string &  
module assembly

# Cryo is a big deal for us

We do not have reasonable sized 2K system available at a big building

- Initially we chose Meson building because of the existence of Meson Cryo Test Facility (CTF) within few 100 ft of Meson Hall, and transfer line
  - It should be able to supply ~60Watts @2K using Vacuum pump from JLab
  - Proton Driver will be using 4K
- In going to New Muon, we will need to come up with a 2nd temporary 2K system
  - This may be either a dewar feed- gas recovery system, or a Satellite Refrig system
  - Again ~40W @2K

## Cryo at NewMuon continued

- We really need ~ 300 W or greater @2K for ILC 4 modules and injector @ 5Hz
- Cryo Plant Study Group
  - Tom Peterson, Fermilab, chair
  - Rau Ganni, Jlab
  - John Weisend, SLAC
  - Joel Fuerst, ANL
  - George Mulholland, consultant
- Should we get a new Cryo Plant a la Rossendorf?
- Or should we make use of the SSC plant (3500 W at 4 K) that ANL has and adapt it for 2K ?
- Report due this month
- No matter what this will take 3 years or greater

# Cryo capacity expected with temporary systems:

Cryo Test Facility (Meson)  
or  
NewMuon

60W@2K useful  
1600w@4K  
40W@2K useful



## Cryo Needs:

Vertical & Horiz dewar test  
Module string & injector

Vert needs large capability ~200W?  
1 Hz, 5Hz see chart

Cryo needs for SMTF-ILC Inj & modules without contingency or dist loss

Typically use  $\sim 1.3 \times 1.5 = 2$

	Rep rate [Hz]	Single Cavity Module		Multi Cavity CryoModule								Capacity Required*		
		Accelerating Gradient, [MV/m]										2K	5K	80K
		12.5	30	15	5	35	35	35	35	35	15			
		Cap Cav	3.9 GHz	8 Cavity Module				4 Cav		3.9 GHz		[watts]	[watts]	[watts]
#1	#2	Acc	Tran	#1	#3	#4	#5	#6	3.9 GHz					
Temporary Cryogenic System	1	X	X	X								9	17	69
	1	X	X	X		X						17	33	207
	1	X	X	X		X	X					26	48	344
New Cryogenic System	5	X	X	X	X	X	X					73	79	1035
	5	X	X	X	X	X	X	X	X			129	124	1854
	5				X	X	X	X	X	X	X	153	155	2330

\* - Capacity required is based on the estimated heat load for  $Q = 5 \times 10^9$


\*\* - No extra capacity or distribution system heat leak is included



# Meson Hall Before and After Cleanup



# NewMuon Building




Must remove  
Chicago Cyclotron  
Magnet

# Phases of ILC Test Facility

From SMTF Proposal

## Phase 1 (FY06-08)



06-07

## Phase 1 FY 06-08

06- 07

- a) 1 Module
- b) with Inj


08

- a) Upgrade Inj
- b) Prepare for 2nd module

08

Build ~ 3 modules, do not expect all to meet gradient


## Phase 2 (08-09)



## Phase 2 08-09

2 Modules & Upgraded Inj  
Build ~ 2 modules

## Phase 3 (FY09-...)



## Phase 3 FY 09-....

- a) Inj & 4 Modules
- b) Inj with 8 cavity module (tentative) & 4 modules

Build ~ >= 1 module

# First Modules- Present thoughts (agreements in process)

- “DESY/FNAL module” Type III plus
  - Parts provided by DESY
  - Cavities tested through Chechia (Horiz Test Dewar) at DESY
  - String & module assembled at FNAL
- “1st US (& international) module”
  - Cavities from Accel, AES, KEK, JLab
  - Cavities processed at JLab (EP), KEK (EP), CU (BCP),FNAL (BCP)
  - Vertical tests JLab, KEK, CU
  - Horizontal Tests FNAL
  - String & module assembly FNAL
- “4th Generation module”
  - Design evolution from TTF Type III
  - Cavity slot length, quad/BPM location, vibration issues, tuner type,..

# Collaboration efforts underway or almost underway (MOUs)

- DESY- CapCav#2, TESLA module, string assembled at FNAL
- JLab - EP Processing, Cavity VDT & dress for HDT, TESLA & 3.9GHz cavity fab, Refrigerator Study
- ANL - BCP Chemistry facility, Refrigerator option
- Cornell - BCP Tesla cavities, VDT
- KEK - 4 cavities for a (2nd) module
- INFN - participate in DESY/FNAL module, 4th generation module development
- LANL?- Develop EP facility plan


# Why Build a Joint Cavity Processing Facility?

## Argonne & Fermilab



**Beta < 0.1**

For two decades  
groups operated  
independently



**Beta = 1**



Rare Isotope Accelerator  
4<sup>th</sup> Generation Light Source



SMTF and International Linear  
Collider (ILC)  
8 GeV Proton Injector




- There has been a convergence of interest in the past decade between the low- and high-beta communities
- (1) Techniques needed to achieve state-of-the-art are similar
- (2) We are filling in the region between low- and high-beta with new cavity types

Mike Kelly

# Layout: ANL/FNAL Cavity Processing Facility




Installation of Cavity Etching Hood 3/25/05





## Support Infrastructure for 1<sup>st</sup> U.S. Built Cryomodule: MP9 Cryomodule Assembly Facility Development

- Building is sufficiently sized for R&D production quantities (1 per month)




# Capture Cavity2 from DESY

Student with project Koeth TuA09



Shipping test with nothing special done - input coupler developed leak



Capture cavity module used at TTFI sent to FNAL.

Low gradient cavity is being replaced with  $>25\text{MV/m}$  cavity

New dressed cavity with beamtubes, gatevalves, etc on its way from DESY (McGee)


Ready for installation in vac vessel without opening to air.

Schedule- mount in vessel Aug, move to Meson Lab Sept and start cryo commissioning

Systems Test at Meson of: Cryo @4K, RF, LLRF, Controls, - in early 06 cryo @ 2K



# Photoinjector Upgrade for SMTF




**Existing FNPL**



Upgrade of existing PI includes:

- 2nd TESLA CapCavity and
- 3.9GHz acc mode "3rdHar" for bunch compression
- 3.9GHz transverse mode for bunch slice diagnostics
- Improved gun & gun modulator



**FNPL Upgrades**

# Schedule Highlights (tentative)


- Begin CapCav#2 tests at Meson 4K Oct 05
- Commission BCP at ANL Jan06
- CapCav#2 operating at 2K Feb 06
- Commission Horiz Test Dewar at Meson April 06
- Cryo Module Assembly Fac ready for string assembly  
May 06
- Move Photoinjector Summer 06
- Temp Cryo System at NewMuon Oct 06
- Begin tests Photoinjector Oct 06
- Complete assembly of 1st Module Dec 06
- Commission Module w Photoinj early 07

# 3.9GHz activities

- Koeth [TuA09](#) SC Cavities at 3.9 GHz
- Solyak [TuP14](#) Recent results of testing 3 cell 3.9 GHz accelerating cavity
- Khabiboulline [ThP50](#) Power coupler design for 3rd Harmonic and spoke cavities
- Mitchell [ThP29](#) Mechanical Design and engineering of the 3.9GHz 3rd Harmonic SRF system

# Two 3.9 GHz cavity developments



- 3rd Harmonic acc mode cavity for bunch compression- linearizes the 1.3 accelerating gradient over the bunch length. To be used at TTF-II (4 cavity module) and PhotoInj Upgrade (single cavity)
- 3.9 GHz deflecting mode cavity for bunch slice diagnostics, momentum or emittance as function of position in the bunch at PhotoInj Upgrade (originally for a pure Kaon beam experiment at FNAL)



# 3.9 GHz acc mode 4 cavity module for TTF (all the design and fab steps by FNAL with help)

## 3.9 GHz Cavities & Cryostat(s): Work in Progress

- Design coldmass supports, both sliding and fixed
- Design coldmass and cryostat
- Main coupler design
- Helium vessel design complete but may need minor revision
- Helium supply pipe redesign (spacing & material)
- Heat Loads and cool-down analysis



Mitchell

## 3.9 GHz processing history and test results- getting our learning curve

- We now have a data base of about 9 test results from each type cavity
  - Help from Kneisel (JLab) and Kelly (ANL) on processing BCP, 600C bake, HPR
  - BCP- JLab, ANL(existing facility), FNAL
  - Oven bake- JLab, FNAL
  - HPR- JLab, FNAL
  - Vert Test - FNAL
- Goal: BCP-ANLnew, Oven bake-FNAL, HPR-FNAL, Test-FNAL, reasonable time turn around
- We now have existence proof using **existing** ANL BCP

## 3.9 GHz Results





(Rs has been the main problem)

- Acc mode-  $E_a \sim 19 \text{ MV/m}$  ( $\sim 105 \text{ mT}$ )  $R_{res} \sim 6-10 \text{ nOhm}$ 
  - This  $19 \text{ MV/m}$  would be equivalent to  $21 \text{ MV/m}$  in a 9cell
  - Design requirement  $14-15 \text{ MV/m}$
  - What is  $E_a$  limit, thermal or not? It is not temp dependent
- Def mode-  $E_{trans} \sim 7.5 \text{ MV/m}$  ( $\sim 120 \text{ mT}$ )  
 $R_{res} \sim 60 \text{ nOhm}$  (best to date)
  - Design requirement  $5 \text{ MV/m}$  transverse
  - We still do not understand high Residual resistance

# 3.9GHz

## Acc mode TM010

## Def mode TM110



# Materials research & with Universities


- Bauer [TuP01](#) A comparison of Q slope models and Data in bulk Nb SRF Cavities
- Bauer [TuP47](#) Recent RRR measurements on Nb at Fermilab
- Boffo [TuP48](#) Eddy Current Scanning at Fermilab
- Boffo [ThP01](#) EP on Small Samples at Fermilab

## University collaborators


- Sebastian [TuP06](#) Atom Probe Tomography
- Lee [Tu54](#) Grain Boundary Flux Penetration & Resistivity in Large Grain Nb Sheet
- Polyanskii [TuP55](#) Magneto Optical Study of Flux Penetration

DESY calibration disc scanned by A. Brinkmann/DESY

# Eddy Current Scanning




Resolution achieved:  
100  $\mu\text{m}$  Ta defects can be detected!




EC-Scanner – on loan from SNS

DESY calibration disc scanned at Fnal, after filtering by C. Boffo




TuP48

## Magneto-Optics at the University of Wisconsin



## 3D Atomic Probe Tomography at Northwestern



J. Sebastian / Northwestern university

3D-AP view of Nb tip with F surface contamination

“Plans are nothing;  
planning is everything.”


D Eisenhower

Results are Best

END

Thanks to all people at FNAL & other Labs  
for helping us get started

# FNPL as Electron Beam source for ILC Test Area



		SMTF proposed (up to)	Present Inj typ
RF pulse length	msec	1.5	0.03-0.6
Pulse rate	Hz	5	1
Beam pulse length	msec	1.0	10-20 micro sec
Beam current	mA	15	10
Electrons per bunch	e10	2	0.6-6.0
Bunch spacing	ns	337	1000
Beam pulse*current	ms*mA	10	0.2

# History of the 3.9GHz 3-cell accelerating cavity

Eacc of 15MV/m = 75mT 9 cell, 13.6Mv/m=75mT 3 cell

Where	BCP	HT	HPWR	Test Date	Test results
FNAL	No	No	No	01/21/04	Rres = 2000nΩ Ea=5.6 MV/m; Hpk( $\pi/0$ )~30/60 mT
JLAB 02/25/04	Extrn~20μm Int ~140μm	2hrs@500 C 10hrs@600C	JLAB 15'@2 loc	03/17/04 04/19/04	Rres=60nΩ → 200nΩ (after FE) Ea=11.5 MV/m; Hpk =60mT; <b>Heavy X-ray</b>
JLAB 06/10/04	Intern: ~30 μm	No	JLAB 30'@3 loc	07/02/04 07/19/04	Rres =70nΩ→130nΩ (after HG) E=12.5 MV/m, Hpk( $\pi/0$ )=70/110mT; <b>X-ray</b>
FNAL 10/10/04	No	No	~1 hrs, movable	10/14/04	R_res=60 nΩ, E=12.8 MV/m, <b>No X-ray</b>
JLAB 10/26/04	Intern: 20μm	No	JLAB 90'@7 loc	11/10/04 12/16/04	E= 5MV/m – vacuum leak E=15MV/m coupler problem
FNAL 01/30 /05	Internal: ~5μ m	No	~2hrs movable	02/08/05 02/21/05	R_res=6 nΩ, E=19MV/m, Hpk=105mT, <b>No X-ray</b>
FNAL 05/25/05	No	48hrs@120C	No	03/31/05	R_res = 16 nΩ, E=19MV/m, Hpk=105mT, <b>No X-ray</b>
ANL 06/01/05	1:1:2 12min(15C)	No →(HPWR 3hrs after BCP) →	FNAL ~2.5hrs	06/09/05	R_res= 58 nΩ, E=12MV/m, Hpk( $\pi/0$ )=62/104mT; <b>X-ray</b>
FNAL 06/25/05	No	No	~6.5 hrs movable	07/05/05	R_res=10nΩ, E~19MV/m, <b>No X-ray</b>