



CESR STATUS

D. RUBIN FOR CESR OPERATIONS GROUP

OCTOBER 15, 2001


- Summary of 4s run
 - Machine configuration
 - Luminosity limit
- Machine Upgrade
 - Positron converter
 - Superconducting IR quads
 - x-ray beam line
- Commissioning
- Operation at $\sim 1.9\text{GeV}$
- Resonance run plan



4S RUN

• Machine Configuration

- Electrostatically separated orbits
- Nine trains with 5 bunches/train in each beam
- $\pm 2.5\text{mrad}$ crossing angle
- 8mA/bunch
- Bunch spacing within each train - 14ns






INTERACTION REGION

- 1.5m REC final focus quadrupole

- Solenoid compensation by rotation of IR quads
- $\beta_v^* = 18\text{mm} \rightarrow 21\text{mm}$
- $\beta_h^* = 94\text{cm}$
- $\sigma_l = 18\text{mm}$

- Parasitic crossing 2.1m from IP -

- Largest vertical tune shift of 89. $\Delta Q_v \sim \frac{I_b \beta_v}{x^2}$






SUPERCONDUCTING RF

- 4- single cell - 500MHz
superconducting RF cavities


T	4.5K
$\langle G \rangle$	6.2MV/m
\hat{V}	7.4MV
I_{total}	750mA
P_{beam}	1.1 MW
P_{HOM}	2.75kW/load
$P_{max}/cavity$	294kW






4S PERFORMANCE

Total beam current	750mA
Non HEP time	~6 minutes/fill
β_v^*	21mm
ξ_v	0.07
Peak luminosity	$1.3 \times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$
$\int L/\text{day}$	73 pb^{-1}
$\int L/\text{month}$	1500 pb^{-1}
11/2000 \rightarrow 6/2001	11.24 fb^{-1}






LUMINOSITY HISTORY






LUMINOSITY LIMITS



- 9 trains with 4 bunches/train
 - $\xi_v \sim 0.07$
 - Tune shift saturates at 7.5mA/bunch
 - Beam-beam limited - increased bunch current \rightarrow poor lifetime and deteriorating specific luminosity



- 9 trains with 5 bunches/train
 - $\xi_v \sim 0.065$
 - Tune shift saturates at 7mA/bunch
 - Specific luminosity decreases with increasing current



PARASITIC BEAM-BEAM INTERACTION


○ Uneven spacing \Rightarrow bunch dependent tune and closed orbit

◇ Closed orbit $x(s) \sim a\sqrt{\beta_h(s)} \sin(\phi_h(s) - \phi_0)$

◇ Long range beam-beam tune shift

$$\Delta Q_h \sim \frac{I_b \beta_h}{x^2} = \frac{I_b}{\sin^2(\phi_h(s) - \phi_0)}$$

Bunch dependent electron positron orbit
difference at IP for first 3 trains with
7.5mA/bunch. $\sigma_y \sim 4\mu$. \rightarrow



Bunch dependent tune shift for first 3 trains
with 7.5mA/bunch. \rightarrow




PARASITIC BEAM-BEAM INTERACTION

- Horizontal tails

- Minimum separation $\sim 7\sigma_x$
- Tails of the bunch approach core of counterrotating bunch \rightarrow large vertical tunes shift and particle losses

- Bunch dependent luminosity

- Bunches at center of train yield 25% higher luminosity than bunches at ends of the train



Separation at parasitic crossing points in units of horizontal rms beam size



PARASITIC BEAM-BEAM INTERACTION

- Compensation of bunch dependent tune and orbit
 - Orbit correction with fast kicker
 - ◇ Adjust closed orbit independently for each bunch
 - ◇ $\sim 1\mu\text{m}$ capability
 - ◇ Mixed result
 - Tune correction with RFQ
 - ◇ $f_{RFQ} = 9 \times f_{ref}$
- More closely spaced bunches
 - Reduce bunch spacing to 6ns and 8ns from 14ns
 - ◇ Sufficient separation near IP?
 - ◇ Simulation indicates tune spread increases more rapidly than total current.



UPGRADE

- Superconducting IR quads
 - Energy reach
- Positron Converter
 - Increased positron production rate
- x-ray beam line



SUPERCONDUCTING IR QUADS

- Objectives

- Extend energy reach
- Reduce β_v^* from 18mm to $< 1\text{cm}$ and β_v at parasitic crossing nearest IP
- Electromagnetic vs PM quad \Rightarrow capability for precise correction of final focus optics and solenoid compensation


- Parameters

- V and H focus quad in each cryostat
- Gradient - 48.4T/m
- Peak field - 6 T
- $I \sim 1225\text{A}$
- Length - 65cm
- All quads rotated 4.5° (solenoid compensation)
- Superimposed skew quadrupoles (fine tuning of solenoid compensation)
- Superimposed dipole (orbit correction)
- Support and remote positioning of cryostat by eccentric cam bearings



Superconducting quadrupole status

- Installed in IR - August-September
- Field quality
 - Skew sextupole moment in Q2 cancelled with resistive corrector located adjacent to cryostat
 - Sextupole moment in Q1 introduces tonality (differential tunes) that is corrected with chromaticity sextupoles





COMMISSIONING

- Alignment of IR quads is critical
- 0.5mm vertical displacement of Q01 \rightarrow 22mm orbit error
- Startup optics
 - $E_{beam}=5.3$ GeV
 - $\beta^* \sim 10$ m
 - $k_{Q1} = -0.1$ (5% nominal)
 - Store beam (10/6) -
 - ◇ Low injection efficiency
 - ◇ Loss of injected particles near IR \Rightarrow high CLEO radiation
 - ◇ Due to high vertical β adjacent to IR low β_h at injection point, coupling
 - Measure and correct orbit
 - ◇ Align IR quads to minimize steerings near IR
 - ◇ Zero all correctors



COMMISSIONING

- Load low β (luminosity optics) at 5.3GeV
 - Measure and correct orbits
 - Measure betatron phase and coupling and begin analysis
 - Calibrate: Measure betatron phase and coupling vs magnet strength
 - $I > 240\text{mA}$
- Load 5.175GeV Υ_{3s} optics 10/15?



G-LINE

- New x-ray beam line

- x-rays from electron beam accessible in already existing facility
- x-rays from positron beam accessible in newly constructed facility, through new opening in tunnel wall

- Wiggler parameters

Number of poles	50
Period[cm]	12
Peak magnetic field[T]	0.8
Gap[cm]	4
Pole width[cm]	11



Y RESONANCE RUN PLAN

$\Upsilon_{3S}, \Upsilon_{1S}, \Upsilon_{2S}, 11/01 \rightarrow 7/02$

	Υ_{3S}	Υ_{1S}	Υ_{2S}	Follow up
Beam Energy[GeV]	5.175	4.7	5.	?
Luminosity[$\text{pb}^{-1}/\text{day}$]	33	23	25	?
Start date	15-Nov-01	1-Feb-02	1-May-02	25-Jun-02
Total [fb^{-1}]	1.2	1.2	0.7	?

- August 2002 - begin transition to 1.9GeV operation with installation of first of 14 1.3m long, 2.1T wigglers
 - Installation of 14 wigglers complete June 2003



MACHINE DEVELOPMENT - ψ'' (1.89 GeV)

• IR

- 20cm permanent magnet quad

$$k = -5.09m^{-2}$$

- Q1 - $k = -1.92m^{-2}$

- Q2 - $k = 1.32m^{-2}$

- CLEO solenoid @ 1.0T

- All IR quads rotated 4.5° about axis


- skew quad coils superimposed on Q1 and Q2 permit compensation of coupling over wide range

• Radiation damping

- $\frac{1}{\tau} \propto E^3 \rightarrow 1/2$ second

- $\epsilon \propto \frac{1}{E^2} \rightarrow \left(\frac{1.89}{5.3}\right)^2 \epsilon_{5.3} \sim 25nm$

- Lower emittance \rightarrow reduced long range beam-beam





MACHINE DEVELOPMENT - ROUND BEAMS

$$\xi = \frac{Nr_e}{\gamma} \frac{\beta}{4\pi\sigma^2} = \frac{Nr_e}{\gamma} \frac{1}{4\pi\epsilon} \quad (1)$$

$$\Rightarrow L = \frac{N\gamma f_c}{r_e\beta} \xi \quad (2)$$


- Emittance limited by IR aperture

- Possible parameters

- $\epsilon = 100\text{nm}$
- $\xi = 0.1$
- $\beta^* = 30\text{mm}$
- $E = 1.88\text{GeV}$

\Rightarrow

- $N = 1.64 \times 10^{11}$, ($I_b = 10.3\text{mA}$)
- $L_b = 2.75 \times 10^{31} \text{cm}^{-2} \text{s}^{-1}$
- $N_b = 7$, $\rightarrow L = 1.9 \times 10^{32} \text{cm}^{-2} \text{s}^{-1}$ (head on)



**CESR-C RUN PLAN**

- **August - September 2002**
 - Install full size wiggler prototype
 - Remove one pair of arc dipoles to make space for wigglers
 - Install CLEO vertex detector
- **October - December 2002**
 - Beam tests with wiggler
 - Explore operation at J/ψ
 - Run CESR at 5.3GeV for x-ray physics
- **January-February 2003**
 - Install 6 additional wigglers
 - Complete installation of cryo-distribution
- **March - April 2003**
 - Beam tests with wiggler
 - Explore operation at J/ψ , small energy spread
- **May - June 2003**
 - Install 7 remaining wigglers



- July 2003 - June 2004
 - ψ'' (3.78GeV) - 2.55 fb^{-1} :255days
 - 5.3GeV/beam for x-ray physics :110days

- July 2004 - June 2005
 - ψ'' (3.78GeV) - 0.5 fb^{-1} :50days
 - Above ψ'' (4.11GeV) - 2 fb^{-1} :205days
 - 5.3GeV/beam for x-ray physics :110days

- July 2005 - June 2006
 - Above ψ'' (4.11GeV) - 1 fb^{-1} :100days
 - J/ψ (3.1GeV) - 1 fb^{-1} :155days
 - 5.3GeV/beam for x-ray physics :110days

- June 2006 - November 2006
 - Follow up