

Operational Status of CESR-c



1. Physics Motivation
2. Introduction to CESR
3. The Beam Dynamics/Lattice Design Challenge
4. Construction/Installation Milestones
5. Superconducting Wiggler Magnets
6. Operational Performance
7. Outlook

Physics Motivation

CLEO-c and CESR-c: A New Frontier in Weak and Strong Interactions CLNS 01/1742 October/2001

Unprecedented statistical precision for decays of charm-quark bound states


Increase world samples of D , D_S and J/ψ decays by more than two orders of magnitude

Take advantage of the opportunity provided by

1. CESR storage ring operation/design experience
2. CLEO detector technology
3. Cleanliness of threshold production kinematics


Depends on solving the damping-dominated beam dynamics design problem

The Cornell Electron Storage Ring Facility



Pretzel Orbits

1430601-002



Beams are horizontally separated at the parasitic crossing points (|||||) by electrostatic separators.

Resulting beam optics distortions require careful lattice design (e.g. sextupoles) to maintain focussing at IP while reducing the parasitic beam-beam interactions.

The Beam Dynamics Challenge (I)

**Consequences of reducing beam energy
5.3 GeV ($\Upsilon(4s)$) \rightarrow 1.9 GeV ($\psi(3s)$)**

For fixed integrated bend radius, $\epsilon_x \propto E^2$ and $\tau_{\text{damping}} \propto E^{-3}$

\Rightarrow Severe consequences for

1. Horizontal emittance ϵ_x and energy spread
2. Injection repetition rate
3. Beam-beam kicks and tune shifts (parasitic crossings !)
4. Single-bunch instability thresholds
5. Intra-bunch scattering

\Rightarrow Induce damping with 12 superconducting wiggler magnets at 2 Tesla peak field

The Beam Dynamics Challenge (II)

The damping effect of the wigglers

Horizontal emittance: 30 \rightarrow 220* nm

Damping time: 570 \rightarrow 55 ms


Energy spread: $2 \times 10^4 \rightarrow 8 \times 10^4$

*Can be tuned with field strength and dispersion at the wigglers


The machine lattice must have sufficiently flexible design capability, e.g. independent quadrupoles, sextupoles, solenoid compensation, to compensate for the non-linear vertical focusing from the wigglers ($\Delta Q_V \gtrsim 0.1$ per wiggler !) for 9 trains of 5 bunches each in pretzel orbits.

The Superconducting Wiggler Magnets

7-pole Wiggler



8-pole Wiggler




7-Pole Wiggler (2.1 T Peak Field, 161 Amps) – Wiggler #1									
Pole Length (cm)	Number	Cutout Width (cm)	Cutout Depth (mm)	Main Current (Amp-turns)	Main Turns	Main Width (Inches)	Trim Current (Amp-turns)	Trim Turns	Trim Width (Inches)
20	5	6	5.0	95.00k	588	1.000	—	—	—
15	2	6	3.5	61.07k	378	0.642	0.86k	663	0.358
7-Pole Wiggler (2.1 T Peak Field, 144 Amps) – Wiggler #2									
20	5	6	5.0	95.00k	660	1.000	—	—	—
15	2	6	3.6	57.00k	396	0.603	4.569k	684	0.380
8-Pole Wiggler (2.1 T Peak Field, 144 Amps) – Wigmeters #3 – #16									
20	4	6	5.0	95.00k	660	1.000	—	—	—
15	2	6	5.5	95.00k	660	1.000	—	—	—
10	2	6	3.6	50.76k	352	0.533	0.993k	836	0.467

Field Quality of the Wigglers


Example: Wiggler SN#6

Integrated vertical field component (gauss-m)




The residual kick is less than a few gauss-meters for an absolute integrated kick of over 10^4 gauss-meters.

Integrated horizontal field component (gauss-m/cm)



The residual skew quadrupole error is less than 2 gauss-meter/cm.

Superconducting Wiggler Magnets in the Ring



APS April Meeting 2004

2 May 2004

CORNELL UNIVERSITY  **LEPP**
LABORATORY FOR ELEMENTARY-PARTICLE PHYSICS


J. A. Crittenden

9



Milestones

- 5/2001 Internal lab program review
- 9/2001 Installed new s.c. focussing magnets in IR
- 5/2002 NSF site visit and review
- 8/2002 **First s.c. wiggler installed in ring**
- 9/2002 Machine studies verify wiggler dynamics
- 10-12/2002 **Engineering run. $I_{\text{Tot}} \simeq 90 \text{ mA}$, $L_{\text{peak}} \simeq 1.0 \times 10^{31} \text{ cm}^{-2}\text{s}^{-1}$**
- 3/2003 NSF project approval through 2008
- 7/2003 New vertex chamber installed in CLEO detector
- 8/2003 **Install five additional wiggler magnets**
- 11/03-4/04 **Physics run. $I_{\text{Tot}} \simeq 110 \text{ mA}$, $L_{\text{peak}} \simeq 3.0 \times 10^{31} \text{ cm}^{-2}\text{s}^{-1}$**
- 4-6/2004 **Install final set of 12 wiggler magnets**

CESR-c Progress in Integrated Luminosity



Examples of Currents and Luminosity



Typical Running Parameters

8×4 bunches

1.5 mA/bunch

$$Q_H = 10.51 \quad Q_V = 9.58$$

$$\epsilon_H = 160 \text{ nm} \quad \epsilon_V = 8 \text{ nm}$$

$$\beta_H^* = 68 \text{ cm} \quad \beta_V^* = 1.3 \text{ cm}$$

$$\sigma_H^* = 330 \mu \quad \sigma_V^* = 10 \mu$$

Crossing angle 2.7 mrad

$$\sigma_E/E = 8 \times 10^{-4}$$

$$I_{\text{Tot}} = 100 \text{ mA}$$

$$L = 2.5 \times 10^{-31} \text{ cm}^{-2} \text{ s}^{-1}$$

Summary and Outlook

- ⇒ 16 wiggler magnets have been built, tested to specification and commissioned.
- ⇒ CESR has operated with six wigglers installed on one side of the ring.
The optical properties of the wigglers were measured to be as expected.
- ⇒ The world supply of $\psi(3770)$ decays was tripled during a 3-month physics run from November/2003 to January/2004.
- ⇒ Peak luminosities of 20% of the design goal have been obtained.
- ⇒ Theoretical limits to bunch current and b-b tune shift have yet to be reached.
- ⇒ CESR operation with the full set of 12 wigglers and the east/west symmetry of the ring restored will begin in August.
- ⇒ Experience to date indicates that mastering multibunch injection and matching/stabilizing electron and positron beam functions at the IR will be key to reaching design goals.

Major challenges ahead for beam physics at CESR-c